



LIMITED TENDER FOR

**SUPPLY & INSTALLATION OF GI ANGLE IRON FENCING POST WITH BARBED WIRE AND CONCERTINA COIL,
AND CIVIL MISCELLANEOUS REPAIR WORK AT BOUNDARY WALL, MDI GURGAON CAMPUS.**

1. **Time schedule for tender process:**

| Sr. No | Description Details | Date and Time |
|--------|---|------------------------|
| 1 | Date of publication of tender notification | 02/09/2025 at 10.00 AM |
| 2 | Last date for receipt of duly filled-in tenders | 17/09/2025 at 03.00 PM |

2. **INTRODUCTION**

Management Development Institute Gurgaon (MDIG), Haryana (hereinafter referred to as the "Institute") is one of the Institute of national repute and is dedicated to offer world class programmes in Management Education. The Institute Invites Sealed Bids on '**Single Bid System**' as mentioned hereunder in the attached prescribed format from reputed agencies having adequate experience in doing similar work.

3. **TENDER NOTICE:**

MDI invites sealed Bids under "Single Bid Systems" (Price Bid only) for "**Supply & Installation of GI Angle Iron Fencing Post with Barbed wire and Concertina coil, and civil miscellaneous repair work at boundary wall MDI Gurgaon**" from the agencies that have adequate experience to carry out similar works. The prospective bidders are advised to read the entire Tender document carefully and satisfy themselves about the work, site conditions by visiting MDI Gurgaon Campus (PI Department), on any working day between 10 a.m. and 5 p.m. before submitting Bids (nothing is payable for visiting the MDI campus in this regard). The sealed bids as specified in the Tender document should be addressed to: -

**The Chief Administrative Officer (IS)
Management Development Institute,
Mehrauli Road, Sukhrali, Gurgaon- 122007"**

so as to reach through speed post/Registered Post/By hand to be dropped in the Tender Box placed at Physical Infrastructure department at TakshaShila building, on or before 3 PM, 17/09/2025.

4. **Submit the following documents:** The participating agencies shall enclose copies of the following documents

- (i) Latest Income Tax Clearance Certificate.
- (ii) Valid GST & PAN registration (Copy attached).
- (iii) ESI, PF registration Certificate, if applicable

5. **Mode of Submission:**

The Bids should be sealed in a cover duly superscribed on top of cover "**Supply & Installation of GI Angle Iron Fencing Post with Barbed wire and Concertina coil, and civil miscellaneous repair work at boundary wall, MDI Gurgaon Campus**".

Any Addendum/Corrigendum, date extension in respect of above Tender shall be updated on MDI Gurgaon website only. No separate notification shall be issued in the press.

6. **Bid validity:**

The Bid submitted by the bidder shall remain valid for 90 days period, to be counted from last date of submission of bid at MDI Gurgaon published in the Tender document


7. **Earnest Money Deposit (EMD):**

1. The Earnest Money Deposit (EMD) of an amount of Rs. 20,000/- in the form of Demand Draft only in favor of **Management Development Institute Society** and payable at **Gurgaon**. EMD will not bear any interest to be paid by MDI Gurgaon.
2. The EMD of unsuccessful tenderer will be refunded within 45 working days, after, award of work to the successful bidder.
3. If the EMD is not enclosed, the Bid will be summarily rejected
4. **Cheque will not be accepted towards EMD.**
5. The Earnest Money Deposit will be forfeited and bidder will be disqualified from participating in any future Tender of the Institute if:
 - a) Tenderer withdraws his bid or backs out after acceptance of Work Order.
 - b) Tenderer violates any of the conditions prescribed in the Tender Document.
 - d) Tenderer requests to revise any of the terms of Tender, during bid validity period or after work.

8. **AWARD OF WORK:** -The Bidder quoting the lowest rate for the Tender shall be considered for Award of Work. However, MDI does not bind itself to accept the lowest or any other bid and reserves the right to accept or reject any or all the bids either in full or in part without assigning any reason or bargain to arrive at reasonable rates.

9. **Terms and conditions are as under: -**

- (i) The price quoted should be inclusive of manpower, material, transportation, unloading, and Construction, and exclusive of GST. The price should be quoted in the price format **Annexure-A** only. For the sample design, please refer to **Annexure B**.
- (ii) The Scope of Work shall include "**Supply & Installation of GI Angle Iron Fencing Post with Barbed wire and Concertina coil, and civil miscellaneous repair work at boundary wall MDI Gurgaon Campus**" as per the sample design enclosed and until final acceptance of the complete work by the Institute.
- (iii) The quantity to be executed may vary according to actual requirements. The payment shall be made on the basis of actual quantity at the rates quoted by the bidder and accepted by MDI Gurgaon, as per schedule of quantities enclosed, items supplied and installed. The agency shall bring only the actual quantity of materials required after measuring the actual area of work to be done at site.
- (iv) Payment will be restricted to actual quantity supplied at site and work executed.
- (v) The entire work should be completed within 60 days of the confirmed order in writing by the Institute.
- (vi) In case the work is not completed within the date stipulated penalty shall be imposed @ Rs. 5000 /- each day of delay, subject to a maximum of Rs.1,00,000/- (Rs One lakh only). However, Director, MDI shall be empowered to grant an extension of time on valid grounds.
- (vii) In case any item is found to be defective /substandard, the same shall be rejected and no amount shall be paid for such items. Such items shall be removed from the site immediately by the agencies, or it will be replaced by MDI Gurgaon at the cost of agency.
- (viii) The work shall be executed as per CPWD specification. The mode of measurement of work done shall also be based on CPWD specification.
- (ix) The agency shall take all safety and security precautions while executing the work for the safety of his employees. The Institute shall not, in any way, be liable for any damage/ liability on account of any mishap or negligence of the agency.
- (x) The agency shall be held responsible for any mishap/accident and liability, if any, falling thereof. The Institute shall in no way be responsible for the same.
- (xi) Water and electricity shall be supplied by the Institute free of cost.
- (xii) The dismantled mulba/rubbish should be disposed off time to time, and on completion of work by the agency outside the campus at the dumping ground approved by MCG, at its own cost. Failure to which, it would be got done by the Institute at the risk and cost of the Agency, and the said amount shall be deducted from the bills payable to the Agency.



- (xiii) If at any stage the bidder agency who has been awarded the work fails to complete the work, the same shall be got done by the Institute through other agency or at market rates, at the cost of the bidder agency who has been awarded the work and will be charged from the bidder agency.
- (xiv) The watch and ward of materials brought at site shall be the responsibility of the Agency. The Institute shall not be responsible for the same.
- (xv) The Agency must get acquainted with the proposed site for the work, specifications, and conditions mentioned in the Tender document before quoting the rates.
- (xvi) **Terms of payment: -**
- No advance payment will be made.
 - 95 % of payment shall be paid to the Agency on submission of original invoices. Only one RA bill be accepted during the complete work.
 - The Balance 5% payment will be retained for one year as Performance Guarantee and will be released after 12 months from the date of successful completion of work to the satisfaction of the Institute. No interest shall be paid by the institute on retention money.
10. The rates are fixed and shall be valid for entire duration of work.
11. The agency shall prepare two complete wall panel samples (up to 6 Mtr approx. with Y angle, Barbed wire & Concertina coil, etc), as per specification provided at Annexure-A and get the sample approved from the Institute.
12. The agency will be responsible for free of cost repair of any damage to the above-mentioned work due to material failure and /or replacement of the item within one-year period of acceptance of the completed work by MDI Gurgaon. No payment request in this regard from the agency will be entertained by MDI Gurgaon. It may be noted that if the agency is unable to take up any such repair/replacement work, MDI Gurgaon shall use retention money held for such repair/replacement purpose.
13. The Institute reserves the right to get the whole or part of work done through one or more bidders.

The quantities indicated in the Schedule of Quantities are approximate only. The quantities can be increased, decreased, or totally deleted while placing work order by the Institute. Payment shall be made for the actual quantity of work done by the agency at site.

MDI reserves the right to accept or reject any or all the bids without assigning any reason whatsoever.

Thanking you,

Yours faithfully,

Chief Administrative Officer (IS)
MDI Gurgaon



Enclosure-Annexure-A & B

FINANCIAL BID PROFORMA

SUPPLY & INSTALLATION OF GI ANGLE IRON FENCING POST WITH BARBED WIRE AND CONCERTINA COIL, AND CIVIL MISCELLANEOUS REPAIR WORK AT BOUNDARY WALL, MDI GURGAON CAMPUS.

(To be printed on the letterhead of the tenderer and to be sealed in an envelope)

| Si. No | SCHEDULE OF QUANTITIES | Unit | Estimated Qty | Rate Rs (without GST) | Total Amount Rs (without GST) |
|--------|---|---------|---------------|-----------------------|-------------------------------|
| 1 | Fabricating, fixing, and welding in position existing available structural steel that is being removed from the boundary wall structural frame and re-fabricated as per the drawing enclosed, all sections viz. angle iron, barbed wire, concertina coil including staging & scaffolding. (Boundary wall from Sukhrali corner to Samriddhi corner length is approx. 450 Mtr) | Lumpsum | 450 Mtr | | |
| 2 | Providing, fabrication and fixing in position angle iron (40x40x6 mm) with making Y shape, 600 mm concertina coil between Y Iron Angle on the wall & welding/fixing with existing angle post, with horizontal rows with stacking at site & reuse available material which is in useable condition, include primer coat and 2 coat of external post on angle post only, including staging & scaffolding. Make- Jindal and Height of Angle from existing boundary wall to 5 ft upper level. | KG | 4800 | | |
| 3 | Providing & fixing in position 2 mm thick (2 no's wires) GI barbed wire with angle post inclusive of GI U-clamps in row (reuse available barbed wire which is in usable condition), including staging & scaffolding. Height of existing boundary wall up to 5 ft upper level. Make- Jindal/Tata | Rmt | 3600 | | |
| 4 | Providing & fixing in position Y-section Concertina coil wire 600 mm dia with angle post, inclusive of GI U-clamps in row (reuse available concertina coil wire which is in usable condition). Height of existing boundary wall to 5 ft upper level of the concertina coil. | Rmt | 450 | | |
| 5 | Providing & fixing in position with angle post expanded metal mesh 2 mm (14-gauge, GI) inclusive of welding of 40x40x6 mm angle frame in row all-inclusive of required material. Height of existing boundary wall to 3 ft upper level of metal mesh. | Sqm | 420 | | |
| 6 | Providing and laying in position specified grade i.e 1:1.5:3 (1 Cement: 1.5 coarse sand: 3 graded stone aggregate 200 mm nominal size) of reinforced cement concrete, including the cost of cantering, shuttering, finishing and reinforcement - All work up to plinth level. | Cum | 2 | | |
| 7 | Providing and applying cement plaster of mix: 1:4 (1 cement: 4 fine sand) up to 15/20 mm. | Sqm | 100 | | |
| | Total | | | | |
| | GST @ -----% | | | | |
| | Total Amount | | | | |

NOTE: Please note that the above includes rates for staging & scaffolding, wherever required. No request for any additional charge from the agency will be considered.



Sign & Stamp of Tenderer



M.S 40x40x6MM Angle Height 600MM



3 Feet MESH JALLI